

Mike Loveless
Raleigh Water

Smith Creek Resource Recovery Facility

Influent Screening, Pumping, and Grit Removal
Improvements



July 25, 2023

Agenda

- Project Background
- Upgrade Mechanical Screens
- Influent Pump Station Improvements
- New Grit Removal System
- Summary
- Questions



04.18.20



INFLUENT PUMP
STATION

2 TON

Project
Background

Smith Creek Resource Recovery Facility (RRF)

Influent Pump
Station

New Grit
Removal

Inf. Flow Measurement



Originally owned and operated
by the Town of Wake Forest

Discharge to Neuse River

Capacity – 3 MGD

Biological Nutrient Removal

Old Grit Removal




Project Scope

Upgrade
Mechanical
Screens

Influent
Pump Station
Improvements

New Grit
Removal
System



Upgrade
Mechanical
Screens

Upgrade Mechanical Screens

- Two existing screen channels – 15' -7" deep
- Isolation gates on each channel
- Unable to completely close gates
- Manual operators on gates





Upgrade Mechanical Screens

- Original Screens
- Rotating Element Screens
- ¼" Openings
- Screen Width 2-feet
- Channel Width 4-feet (concrete inserts on side of channel)
- Unsatisfactory Performance
- Nearing end of useful life
- Not sized for future expansion

Upgrade Mechanical Screens

- Proposed Improvements
- Install new gates with motor actuators
- Install second influent pipe (plugged) for future expansion
- Replace screens and washer compactors with newer technology



Upgrade Mechanical Screens

- Selected Screens
- Duperon Flexrake (Catenary Multi-Rake)
- $\frac{1}{4}$ " openings between bars
- Screen Width 4-feet
- Capacity – 10 MGD each
- All stainless-steel construction





Upgrade Mechanical Screens

- Screenings Washer/Compactors
- Duperon
- One washer/compactor per screen
- Washer/compactor discharge chute to roll-off container
- Wheels and flex connections for maintenance

03/14/20

Upgrade Mechanical Screens

- Startup and Operation



The image shows an industrial setting, likely a pump station. On the right, there is a large, vertical, grey metal pump assembly with various flanges, bolts, and a handwheel. A white label with the word "CAUTION" is attached to the pump. To the left of the pump, several grey pipes run horizontally across the wall, with some bundled together. A fluorescent light fixture is mounted on the ceiling. In the foreground, there is a red and black control panel or enclosure. The overall scene is somewhat dimly lit and has a slightly hazy quality.

Influent Pump Station Improvements

Influent Pump Station Improvements

- Original Influent Pump Station
 - Screening upstream of IPS
 - Wetwell/Drywell
 - Self-Priming Pumps in Drywell
 - Pump to Parshall flume
 - Grit Removal downstream of flume
-



Influent Pump Station Improvements




- Drivers for conversion
- Increased pump head due to higher elevation of new grit removal
- Wetwell problems, including surface vortex and pump cavitation (from air entrainment)
- Frequent maintenance needs of Self-Priming pumps
- Poor operation with VFD's, resulting in "slugging" of treatment process
- Raleigh preference to move away from Self-Priming Pumps


Influent Pump Station Improvements

Existing Wetwell

- Offset influent pipes
- No baffles in wetwell
- Limited wetwell storage
- Constant speed pumps




Influent Pump Station Improvements



- Convert to Submersible Wetwell configuration
- Add baffling to wetwell
- Convert drywell to pipe gallery
- Raise operating levels
- Addition of VFD's
- Modified operating sequence
- Future expansion to include parallel wetwell and force main

Influent Pump Station Improvements


Wetwell Baffling



Courtesy of Clemson Engineering Hydraulics

Influent Pump Station Improvements

- A physical hydraulic model was used to simulate wetwell issue
- Modeling was performed by Clemson Engineering Hydraulics in Anderson, SC
- Model testing recommended wetwell baffles and floor cones to eliminate pre-swirl, uneven flow distribution, air entrainment, and floor vortex activity






Influent Pump Station Improvements

- Baffle wall with inlets and inlet baffles to direct flow downward
- Floor cones installed under each pump

Influent Pump Station Improvements

Drywell piping reconfigured
to connect pump discharge
to station discharge header



The image shows three large, light-colored metal enclosures for Variable Frequency Drives (VFDs) installed outdoors against a concrete wall. Each enclosure has two doors with multiple control buttons and indicator lights. To the left is a dark door with a window. The background features green trees under a clear sky. A semi-transparent text box is overlaid on the right side of the image.

Influent Pump Station Improvements

VFD's in climate-controlled
enclosures installed
outdoors since no available
space in building

05/11/20



Influent Pump Station Improvements

- Grating with access panels for new submersible pumps
- Combination air valves installed in pump discharge piping to release air and break siphons upstream of check valves
- Combination valves installed outdoors to prevent gas release in drywell




Influent Pump Station Improvements

New submersible pumps being
lowered into place


1 Pump Running

- Full Speed 3500 gpm
- Reduced Speed 1000 gpm




3 Pumps Running

Full Speed 9,000 gpm



IPS Control Modifications

- Lead pump starts at reduced speed (49% of full speed)
- Lead pump ramps up as level rises
- Lag pump starts at reduced speed when level is rising and lead pump hits 60hz speed
- Lead and lag pump speeds are matched and adjusted equally as level varies




Influent Pump Station Improvements

- Pump Startup
- Flowrates without new grit removal (reduced head, higher flow)
- Flowrates with new grit removal (increased head, design flow)
- Testing
 - Availability of water
 - Plant capability to accommodate full flows
 - Need to fill wetwell completely




Influent Pump Station Improvements



BEFORE PROJECT

- Erratic flow patterns due to starting and stopping of pumps
- Negative impacts to downstream processes

Influent Pump Station Improvements



AFTER PROJECT

- Smoother flow patterns excepting early morning hours
- Reduced negative impacts on downstream processes

A photograph of an industrial facility, likely a wastewater treatment plant, featuring concrete structures, pipes, and a tall vertical pipe. The site is surrounded by green grass and trees. A black safety barrier with 'RAM TOOL' branding is in the foreground. A semi-transparent white box on the right contains a bulleted list of improvements. The date '05/11/20' is visible in the bottom right corner.

Influent Pump Station Improvements - Summary

- Conversion to submersible pumps greatly improved pump efficiency and allowed better pump turndown
- Wetwell modifications eliminated vortex and air entrainment issues
- Elimination of plant “slugging”
- Improved treatment plant performance

05/11/20




New Grit Removal Facilities

11/29/2021

New Grit Removal Facilities

- Original Grit Removal Facilities
- One Rolling Grit Removal Basin
- Air induction at center creates “rolling” action
- Air Lift Pump
- One grit washer




New Grit Removal Facilities

- Why Replace?
- Old technology
- Equipment at end of useful life
- Location in Hydraulic Profile not compatible with plan for future equalization



New Grit Removal Facilities

- Incorporate stacked tray or “headcell” technology
- Unit specified to capture and retain 95% of all wastewater grit 75 micron and larger
- Structure set at higher elevation to allow for future equalization
- Unit sized for future expansion (Peak Flow 19 MGD)
- Existing grit removal remained in service until construction complete



New Grit Removal Facilities

- New Grit Removal Facilities
- One **Hydro** International HeadCell® Grit Separator (no moving parts)
- Two **Hayward-Gordon** recessed impeller Grit Pumps
- Two **Huber COANDA** Grit Washing Plants





New Grit Removal Facilities

- Hydro-International HeadCell® Grit Separator
- Tray Diameter – 12 feet
- Number of Trays – 10
- Unit Peak Flow – 19 MGD
- Unit Average Flow – 6 MGD
- No modifications needed if plant is expanded to 6 MGD capacity

11/30/2

New Grit Removal Facilities

- HeadCell® Startup Issues
- Constructed out of flow path
- Yard Piping Modifications



11/29/2021



New Grit Removal Facilities

- HeadCell® Startup Issues
- Drain and inspect every 6 months

05/11/2021

New Grit Removal Improvements - HeadCell[®] Results



Table 4.1
Smith Creek RRF Headcell Performance Summary

Size Fraction (μ)	Trial No. 1 (% Removal)	Trial No. 2 (% Removal)	Trial No. 3 (% Removal)
>297	99.9	99.9	99.9
210< SF <297	100.0	100.0	100.0
149< SF <210	99.9	100.0	100.0
105< SF <149	99.8	99.9	99.9
74< SF <105	99.7	99.8	99.9
53< SF <74	99.6	99.8	99.9
All Sizes	99.8	99.9	99.9
$\geq 74 \mu$	99.9	99.9	99.9

New Grit Removal Facilities

- New Hayward Gordon TORUS XR3 Recessed Impeller Pumps
- Two pumps installed to provide redundancy
- Capacity – 300 gpm at 21.5 feet total head
- Woods variable speed V-belt drives (No VFD's)
- Interconnected piping (suction and discharge)



New Grit Removal Facilities

- Grit Pump Startup Issues
- Adjusting Pump Speed
- Variable Speed V-Belt Drive
- Seal Water



05/11




New Grit Removal Facilities - Summary

Pump Summary Items

New Grit Removal Facilities

- Huber COANDA RoSF4-2 Grit Washing Plant
- Two units
- Varying velocities in “tulip” (inverted cone) promote grit separation
- Fluidized bed for improved organics removal



New Grit Removal Facilities

- COANDA Startup Issues
- Feed Rate
- Feed Schedule
- Seeding
- Organics Removal Settings

05/11/2

New Grit Removal Facilities

- COANDA Startup Issues
- Trial and error process
- Unit Leveling



New Grit Removal Facilities

- COANDA results?
- Performance test not performed yet



New Grit Removal Facilities – Summary

- System Summary
- Lessons learned



05/11/2022

Summary

- Project Costs
- Engineer's OPCC – \$5,964,400
- Contract Bid Price – \$5,612,888
- Final Contract Amount – \$5,557,998



Questions?

Special Thanks To:

- Smith Creek RRF Staff
 - John Silveri
 - Dan Hackney
- Raleigh Water Construction Representative
 - Mark O'Grady
- CDM Smith – Design and Construction Administration
 - Ross Stroud, Project Manager and Lead Design Engineer
 - Dan Williams, Lead Designer and Construction Administration

